KOLAR DIVISION.

Dated 23rd December 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 24th January 1931, for restoring Vasanthapur Chennammanakere Tank, Regd. No. 24 of Bagepalli Taluk, Kolar District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred (Rs. 400) only, in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Vasanthapur Chennammanakere Tank, Regd. No. 24 of Bagepalli Taluk, Kolar District," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderer must quote specific rates for all items both in words and figures.

10. Tenders stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate of quantities for restoring Vasanthapur Chennammanakere Tank, Registered No. 24 of Bagepalli Taluk.

No.	Items of work	Per	Quantity
	Bund.		
1	Earthwork to breach with lead and lift including watering and tamping.	C.yd.	4,568
2	Puddle wall	,,	503
3	Earthwork excavation for form out puddle wall	,,	146
4	Surki mortar concrete	C.ft.	463
5	Size stone masonry core wall	,,	4,251
6	Resetting old stone with new jelly	C.yd.	863
7	New stone work	,,	1,493
8	Turfing	S.yd.	4,881
9	Fixing new grade stones	No.	9
10	Do Index stones	,,	9
11	Do Registered number stone...	,,	1
12	Do Gauge stone	,,	1
13	Carving B. M. figures on natural rock	,,	2
	Sluice.		
1	Examining and repairing the existing sluice and providing plug and rod with locking arrangement.	L. S.	Rs.
	Waste Weir.		
1	Dismantling the existing masonry and removing debris ...	C.ft.	518
2	Providing coping slabs 6" thick dressed and fixing in cement ...	S.ft.	92
3	Levelling natural rock by chiselling	,,	40
4	Benching rock 6"	,,	16
5	Draft clearing in rock 6" deep	,,	80
6	Sundry repairs to the return	L. S.	Rs.
7	Resetting old stone of existing apron	Cyd.	23